(*e*) That he shall have no right whatsoever over the block and over the bamboos paid for but left unremoved in any of the blocks after 31st December 1932.

(*f*) That he shall accept the minimum quantity fixed in the notification as available in the block concerned and shall have no claim on the department for any deficit that may be found. If he removes any quantity above the minimum fixed with the lease period, he shall pay for the excess quantity at tender rates.

(*g*) That he shall abide by such orders as the District Forest Officer may issue regulating the transport of bamboos to and collection at their rafting stations.

(*h*) That he shall abide by the rules of the department as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*i*) That he or his men shall not enter the forest after sunset and before sunrise.

(*j*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of bamboos removed and shall keep it open for the examination of Forest Officers above the grade of guards.

(*k*) That he understands that the sale does not prohibit the issue of retail licenses at seigniorage rates or the exercise by the villagers of their rights in the Forests.

(*l*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of cancellation of contract enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

H. V. RANGASWAMY IYENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

WATER SUPPLY DIVISION.

Tender Notification dated 17th February 1932.

Sealed tenders accompanied by an earnest money of Rs. 100 in cash will be received by Executive Engineer, Water Supply Division, Bangalore, at his office up to 4 P.M., on 15th March 1932, for cutting and removing 450 well-grown jally trees and 25 Casuarina trees at Holali near Mulbagol, Kolar District. The acceptance of the tender is however subject to the following conditions and the accepted tenderer should bind himself by a mutchalika and a proper deposit to abide by the same.

1. The period of lease of the rights of cutting and removing will be for three months commencing from 1st April 1932 to the end of June 1932

2. The tenderer shall be bound to cut only the numbered trees as stated below in (11) and 1½ feet of stem should be left above ground level. The quantity cut in a day shall be removed within 24 hours.

3. The cut wood shall not be allowed to be stacked in such a place as will cause any damage to the bund of the tank.

4. No refund will be allowed on any account.

5. No right will be with the lessee for any extension of the terms of lease or the cessation thereof on account of any floods or droughts or any abnormal seasonal conditions.

6. The approved tenderer shall deposit the whole amount on the day of acceptance of the tender by the Executive Engineer and who will issue orders for commencing the cutting and removal.

7. Should the tenderers fail to satisfy any of the above conditions then they shall be liable to forfeiture of the earnest money to the Government.

8. The tenderers are also notified that for the sake of cutting arrangements to be made they ought not in any manner to cause the pollution of the river or tank water by commiting any insanitary acts, nuisance, etc., nor any encroachments on the water by opening out channels, drains and so on.

9. The earnest money will be refunded to the tenderers whose tender is not accepted, after the day of opening tenders.

10. The trees to be cut are numbered. Only the numbers specified should be cut 450 Jally Trees all numbered. Twenty five Casuarina Trees (except numbers 31, 29, 23, 27, 15 and 10 which are reserved for Government use).

11. The decision of the Executive Engineer shall be final on matters connected with this tender.

It is hereby notified for the information of the public that certain unserviceable stores, such as Surveying and Mathematical Instruments, Tools and Plant, office and bungalow furniture, etc., will be sold by public auction on such dates and places as noted below against each Sub-Division:—

Name	Date of sale	Time of auction
Head Quarters, Stores, Bangalore ..	15th March 1932 ..	9 A.M.
Chamarajendra Water Works, Bangalore ..	Do ..	Do
Vani Vilas Water Works, Mysore ..	Do ..	Do
Kolar Gold Fields Water Works, Bethamangala	19th Do ..	5 P.M.

2. For further particulars apply to the Executive Engineer, Water Supply Division, Bangalore, during office working days between 11 A.M. to 5 P.M.

H. F. MARKER,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 15th February 1932.

Subject.—Opening of a new road from 1—71 of Bangalore-Honnavara Road to Kallur up to Ammasandra in Gubbi Taluk.

Attention of the public is drawn to the notification, calling for tenders for the above work in pages 178 and 179, Part VI of the *Mysore Gazette*, dated the 18th February 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 5 P.M. of 13th March 1932.

3. An earnest money of Rs. 250 should accompany the tender.

Notice dated 26th February 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 26th March 1932, for Restoring Padavagere Minor Tank Reg. No. 71—163 in Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1932.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5. P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in figures and in words.

4. Each tender must be accompanied by a deposit of rupees two hundred only (200) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Padavagere Minor Tank Regd. No. 71—163 of Kunigal Taluk. " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates for above or below the estimate amount will not be accepted.

10. No claim for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final, and legally binding on the contractors.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modifications as per data worked out during execution. For individuals items of work under lumpsum provisions the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Excutive Engineer.

Abstract of quantities for restoring Padavagere Tank, Reg. No. 71—163 Kunigal Taluk.

Sl. No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs.	
1	Clearing jungle on bund	Grade	32		
2	Cutting steps and grips in old bund and also in the weir gaps,	L. S.	...		
3	Earthwork to bund including lead and lift, watering, forming, etc., complete.	Cyds. ..	7,995		
4	Earthwork for the breach, left of waste weir with good and selected earth including watering forming etc., complete.	„	390		
5	Turfing the slopes of bund	Syd.	7,226		
6	Painting and figuring the grade stones ...	Each	32		
7	Providing and fixing B. M. Stones with figures cut and painted.	„	2		
8	Register No. Stone do	„	1		
9	New Rough stone revetment to the bund ..	Cyd.	348		
10	Removing and resetting old stones wherever necessary.	„	200		
11	Sluice cut-opening and refilling the bund after making necessary repairs if possible, or to construct a new one if necessary.	No lumpsum amounts need be mentioned. Work done to be paid for as per details to be worked out at rates tendered or as per schedule rates.			
12	Waste weir, 130 ft. long, repairs to the existing waste weir such as resetting apron here and there, patch repairs, etc.				

A. TANDONI RAO,
Executive Engineer.

KOLAR DIVISION.

Dated 25th February 1932.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., of 19th March 1932, for the work of restoring Muthukapalli Majira Kodipalli Minor Tank, Registered No. 608—214 of Srinivasapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and eighty (Rs. 180) in cash or Currency Notes, as earnest money, and be superscribed "Tender for the work of restoring Muthukapalli Majira Kodipalli Minor Tank, Registered No. 608—214 of Srinivasapur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6 Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Percentage rates will not be accepted.

Abstract estimate for restoring Muthukapalli Majira Kodipalli Minor Tank, Register No. 608—214 of Srinivaspur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	Bund.				
1	Earthwork watering and tamping including lead and lift.	C.yd.	0 4 0	3,573	893
2	Turfing	S.yd.	0 1 0	3,755	235
3	Resetting old stone with new jelly	C.yd.	0 12 0	290	218
4	New stone work	,,	2 0 0	688	1,376
5	Fixing grade stones including figuring and painting.	No.	1 8 0	19	29
6	Do Index stones do ..	,,	0 8 0	19	10
7	Do gauge stones do ..	,,	15 0 0	1	15
8	Do B. M. stones do ...	,,	3 0 0	2	6
9	Do Register No. stones do ...	,,	3 0 0	1	3
10	Cutting pipes and removing top soil removing ant hills and refixing.	Grade	4 0 0	16	64
	Total to Bund ...	...	...	...	2,849
	Sluice at 45·00 R. L.				
1	Earthwork excavation	C.yd.	0 4 0	55	14
1a	Do refilling	,,	0 3 0	60	11
2	Concrete in surki mortar	C.ft.	0 4 6	341	96
3	Burnt brick in surki mortar	,,	0 5 0	301	94
4	Burnt stone slabs 6" thick	S.ft.	0 6 0	233	87
5	Surki mortar plastering	Sqr.	4 8 0	572	25
6	Drilling holes	Lump sum		...	10
7	Providing plug and rod with locking arrangement	Lump sum		...	20
	Total to sluice ...	...	..	...	357
	Weir.				
1	Earthwork excavation	C.yd.	0 4 0	114	29
2	Concrete in surki mortar	C.ft.	0 4 6	253	71
3	Burnt brick in surki mortar	,,	0 5 0	288	90
4	Burnt stone slabs 6" thick dressed	S.ft.	0 6 0	385	144
5	Surki mortar plastering	Sqr.	4 8 0	5·52	25
6a	Apron new stone work	C.yd.	2 0 0	48	96
b	Providing stone jelly filling 6" for apron ..	,,	0 12 0	16	12
7	Draft and approach clearing	Lump sum		...	30
8	Providing jaggles	No.	1 0 0	14	14
	Total to weir ...	...	...	...	511
	Total Bund, Sluice and Weir ...	...	...	...	3,717

Notice dated 26th February 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 19th March 1932, for the work of restoring Santhehalli Nidaghattadakere Minor Tank Reg. No. 520/502 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty (Rs. 250) in cash or currency notes as earnest money, and be superscribed "Tender for the work of restoring Santhehalli Nidaghattadakere Minor Tank Regd. No. 520/502 of Malur Taluk" in default of which, tenders will be rejected.

5 The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates will not be accepted.

Abstract estimate for restoring Santhehalli Nidaghattadakere Minor Tank Regd. No. 520/502 of Malur.

No.	Items of work	Unit	Rate	Quantity	Cost
	BUND R. L. 56·00.		Rs. a. p.		Rs.
1	Jungle clearing roots entirely grubbed up ...	Gr.	3 0 0	15	45
2	Removing ant hills and fixing with sand ...	No.	1 0 0	5	5
3	Cutting and removing roots of big honge trees ...	,,	2 8 0	120	300
4	Cutting trenches in old bund	Grade No.	4 0 0	15	60
5	Earthwork to bund including watering and tamping.	C.yd.	0 4 0	4,581	1,145
6	Turfing	S.yd.	0 1 0	4,177	261
7	Resetting old stone revetment with jelly backing and wedging.	C.yd.	0 12 0	198	148
8	Rough stone revetment new including 5 to 6 miles lead.	,,	2 4 0	1,387	3,121
9	Providing new grade stone with Index stones including chiselling, cutting figures and painting.	No.	2 0 0	22	44
10	Providing Regd. No. Date stones including chiselling, cutting figures and painting.	,,	2 8 0	2	5
11	Providing gauge stone including chiselling, cutting figures and painting.	,,	15 0 0	1	15
12	Conveying B. M. stones from Malur T. B. a distance of 5 miles and fixing including painting.	,,	3 8 0	2	7
	Total to bund ...	...	...	...	5,156
	SLUICE R. L. 45·00				
1	Earthwork cutting open the bund	C.yds.	0 4 0	89	22
2	Refilling the earth with watering and tamping ...	,,	0 3 0	80	15
3	Dismantling old brick masonry	S.ft.	Lump	sum	20
4	Stone jelly concrete in surki mortar ...	C.ft.	0 4 6	229	64
5	Burnt brick in surki mortar	,,	0 5 6	420	144

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Burnt stone slabs 6″ thick dressed	S.ft.	0 6 0	437	164
7	Plastering with surki mortar	Sqr.	4 0 0	6·18	25
8	Providing new plug and iron road with locking arrangements complete.	No.	15 0 0	1	15
9	Cutting holes in slabs for orifice plug iron rod ...	,,	1 0 0	3	3
	Total to sluice ...	...	...	...	472
	LEFT WASTE WEIR AT R. L. 51·00.				
1	Earthwork excavation in gravelly soil and using the same for bund, etc.	C.yd.	0 4 6	100	28
2	Concrete in surki mortar	C.ft.	0 4 6	304	85
3	Burnt brick in surki mortar	,,	0 5 6	610	210
4	Burnt stone slabs 6″ thick dressed	S.ft	0 6 0	162	61
5	Plastering with surki mortar	Sqr.	4 0 0	4·57	18
6	Rough stone work new	C.yd.	2 8 0	69	172
	Total to waste weir ...	...	...	...	574
	Total bund, sluice and waste weir ...	...	...	...	6,202

Notice dated 26th February 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 19th March 1932, for the work of restoring Yeraigeripalli Pandigaddalakere Minor Tank Regd. No. 611 of Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty (Rs. 250) in cash or currency notes as earnest money and be superscribed "Tender for the work of restoring Yeraigaripalli Pandigaddalakere Minor Tank Regd. No. 611 of Chintamani Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates will not be accepted.

6 c

Abstract estimate for restoring Yeraigaripalli Pandigaddalakere Minor Tank Regd. No. 611 of Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	BUND R. L. 55·00.		Rs. a. p.		Rs.
1	Earthwork watering and tamping, etc., complete	C.yds.	0 4 0	3,037	759
1a	Gravel backing to revetment ...	C.yd.	0 12 0	356	267
2	Removing and resetting old stone revetment ...	,,	0 10 0	851	532
3	New stone revetment to bund with jelly packing and wedges.	,,	1 12 0	711	1,244
4	Turfing to bund	S.yds.	0 1 0	3,966	248
5	Grade stones including Zero stones cutting, figuring, painting, etc., complete.	Each	1 8 0	17	26
6	Do Index stones	,,	0 8 0	17	9
7	Register No. stone	,,	3 0 0	1	3
8	Gauge stone	,,	15 0 0	1	15
9	B. M. stone	,,	3 0 0	2	6
10	Clearing the bund by removing ant hills and ordinary jungle.	Grade	5 0 0	10	50
11	Removing top soil and cutting grips, etc. ..	,,	6 0 0	10	60
	Total to bund ...	...	..	...	3,269
	SLUICE R. L. 42·00.				
1	Earthwork excavation for foundation ...	C.yd.	0 4 0	84	21
2	Refilling earth with consolidation as per execution	,,	0 3 0	80	15
3	Surki concrete	C.ft.	0 4 6	449	125
4	Burnt brick in surki mortar	,,	0 5 0	509	155
5	Burnt stone slabs 4" to 6"	S.ft.	0 6 0	238	89
6	Plastering with surki mortar	Sqrs.	4 0 0	7·17	29
7	Providing wooden plug with rod with locking arrangements.	Each	15 0 0	1	15
8	Dismantling Debri removal of old sluice No. 2 ..	,,	30 0 0	2	60
9	Gravel mixing in front slope of bund of sluice ..	Lump	sum	Rs.	9
	Total for 1 sluice ..	..	...	...	518
	For 2 sluices ...	..	...	...	1,036
	WASTE WEIR R. L. 50·00.				
1	Earthwork excavation foundation	C.yd.	0 4 0	40	10
2	Concrete in surki mortar	C.ft.	0 4 0	388	97
3	Burnt brick in surki mortar	,,	0 5 0	517	162
4	Burnt stone slabs	S.ft.	0 6 0	542	203
5	Plastering with surki mortar	Sqrs.	4 0 0	7·02	28
6	New stone work	C.yd.	1 12 0	93	163
7	Draft clearing	Lump	sum	Rs.	20
8	Approach clearing and using to bund ...	C.yd.	0 6 0	650	244
9	Providing joggle joints at every 8 feet ...	..	1 0 0	17	17
	Total to weir ...	..	...	...	944
	Total Bund, Sluice No. I and II and Waste Weir ...	..	...	..	5,199

C. T. NARASIMHA IYENGAR,
Executive Engineer.